# BRUHATH BENGALURU MAHANAGARA PALIKE
**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

## MODIFIED APPROVED TENDER SCHEDULE –'B'

Item No: 03

Name of Work:- Improvements to balance main and cross roads of BHEL Layout in Attur ward no 03

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri G KISHORE NAIDU | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no141,PWD SR 2016-17) | Cum | 104.00 | 82.38 | Rupees Eighty Two and Pais Thirty Eight Only |
| 2 | KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications (Item no17.1,Page no133,PWD SR 2016-17 | Cum | 104.00 | 68.31 | Rupees Sixty Eight and Pais Thirty One Only |
| 3 | KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17) | Cum | 15.60 | 4612.94 | Rupees Four Thousand Six Hundred Twelve and Paise Ninety Four Only |
| 4 | Providing and laying plain/reinforced cement concrete for side drains wall and bottom thickness 15 cms using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centering shattering cost of materials HOM f machineries curing etc., complete excluding cost of steel as per MORTH specification | Cum | 43.92 | 9864.70 | Rupees Nine Thousand Eigh Hundred Sixty Four and Pais Seventy Only |

| | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri G KISHORE NAIDU | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46) | Quintal | 30.98 | 5763.29 | Rupees Five Thousand Seven Hundred Sixty Three and Paise Twenty Nine Only |
| 6 | RCC precast covering slab for drain (10 cm thick) | Sqm | 57.75 | 1990.38 | Rupees One Thousand Nine Hundred Ninety and Paise Thirty Eight Only |
| 7 | Providing precast slab of 260 mm thick including cist of all materials labour curring transportation , loading unloading etc., complete as per the direction of engineer incharge. | Sqm | 27.00 | 4844.21 | Rupees Four Thousand Eight Hundred Forty Four and Paise Twenty One Only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.